



PLAN VIEW

CONNECTION SCHEDULE OF OPENINGS

MARK	SIZE/RATING	SERVICE	ELEVATION
A	14"-300# RF	1ST STAGE INLET	53 9/16"
B	12"-600# RF	1ST STAGE DISCHARGE	11 7/8"
C	12"-600# RF	2ND STAGE INLET	51 1/16"
D	10"-900# RF	2ND STAGE DISCHARGE	13 13/16"
E	1" NPT	SCRUBBER DRAIN	3 3/16"
F	2" NPT	COMPR. OIL OUT TO COOLER	3 11/16"
G	2" NPT	COMPR. OIL IN FROM COOLER	3 11/16"
H	1" NPT	COMPR. OIL MAKE-UP	3 3/16"
I	1 1/2" NPT	COMPR. OIL DRAIN/FILL	3 7/16"
J	1" NPT	INSTRUMENT AIR SUPPLY	3 3/16"
L	1" NPT	COLLECTION POT DRAIN	-17"
N	6"-150# RF	PSV HEADER OUTLET	8 3/4"

NOTE:
UNLESS OTHERWISE NOTED,
ALL ELEV. DIMS ARE FROM
TOP OF SKID DECK PLATE.

NOTICE: THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION AND IT SHALL NOT BE USED OR REPRODUCED OR ITS CONTENTS DISCLOSED, IN WHOLE OR IN PART, WITHOUT THE PRIOR WRITTEN CONSENT OF A G EQUIPMENT CO.

				DESCRIPTION: GENERAL ASSEMBLY ARIEL JGC6 W/ 5000HP MOTOR				A G EQUIPMENT PROJECT: 11379-381			
REVISIONS				REVISIONS				DRAWN BY	LN	02/03/2012	
NO	DATE	DESCRIPTION	BY	NO	DATE	DESCRIPTION	BY	CHECKED BY	JAL	02/03/2012	
05	05/08/2012	ADDED SCRUBBER 2" NPT SIGN GLASS CONN.	LN	00	02/03/2012	FOR CUSTOMER REVIEW/ PULSATION STUDY	LN	PROJECT ENG.	JAL	02/03/2012	
06	06/12/2012	AS BUILT	LN	01	02/20/2012	PER PULSATION STUDY	LN	APPROVED BY			
				02	03/02/2012	PER ENGINEER	LN	CERTIFIED BY			
				03	04/17/2012	REVISED DRAIN SUMPS AND PUMP	LN				
				04	05/01/2012	MECHANICAL STUDY/REL. FOR FAB.	LN				

APPROX. TOTAL UNIT WEIGHT: 211,200#
ESTIMATED UNIT SHIPPING WEIGHT: 156,240#



BROKEN ARROW, OKLA. 74012 • PHONE 918-250-7386 • FAX 918-250-7393

SCALE: 1/2"=1'-0"	CUSTOMER P.O. NO.: 210150-DW222	SHEET: 2 OF 4
CUSTOMER: CAIMAN ENERGY, LLC	PROJECT: FORT BEELER PLANT REJECTION	
DRAWING NUMBER: 11379-A1A	ISSUE: 06	